

SUMMARY OF QUANTITIES

**CONSTRUCT EXECUTIVE HANGAR (4 UNITS)
ALTERNATE 1**

**DINWIDDIE COUNTY AIRPORT
PETERSBURG, VA**

**AIP PROJECT NO. 3-51-0039-PENDING
DELTA PROJECT NO. VA 08100**

DATE: 5/28/10

ITEM NO.	SPEC. NO.	DESCRIPTION	UNIT	QUANTITY
1	P-100	MOBILIZATION	LS	1
2	P-140	PAVEMENT REMOVAL	SY	6,085
3	P-150	MISCELLANEOUS DEMOLITION	LS	1
4	P-150	BUILDING DEMOLITION	LS	1
5	P-152	UNCLASSIFIED EXCAVATION	LS	1
6	P-152	UNSUITABLE EXCAVATION	CY	1,000
7	P-156	EROSION AND SEDIMENT CONTROL	LS	1
8	P-405	GROUND STABILIZATION FABRIC	SY	2,000
9	M-107	AVIATION BARRICADES	LF	600
10	M-122	3/4" CLASS 200 HDPE WATER LINE	LF	80
11	M-122	1" CLASS 200 HDPE WATER LINE	LF	435
12	M-122	3/4" CORPORATION STOP	EA	4
13	M-122	3/4" CURB STOP	EA	4
14	M-122	WATER APPURTENANCES	LS	1
15	M-122	8" SDR 35 SANITARY SEWER	LF	130
16	M-122	6" SDR 35 SANITARY SEWER	LF	200
17	M-122	4" SDR 35 SANITARY SEWER LATERAL	LF	75
18	M-122	SANITARY SEWER MANHOLE	VF	20
19	M-122	SANITARY SEWER FRAME & LID	EA	2
20	M-122	SANITARY SEWER CLEANOUTS	EA	4
21	M-208	EXECUTIVE HANGAR MATERIALS (4 UNITS)	LS	1
22	M-208	EXECUTIVE HANGAR ERECTION (4 UNITS)	LS	1
23	M-208	EXECUTIVE HANGAR FOUNDATION (4 UNITS)	LS	1
24	M-208	EXECUTIVE HANGAR ELECTRICAL (4 UNITS)	LS	1
25	M-208	EXECUTIVE HANGAR RESTROOM	EA	4
26	P-620	PERMANENT PAVEMENT MARKING	SF	1,050
27	D-701	15" RCP, CLASS III	LF	198
28	D-701	18" RCP, CLASS III	LF	112
29	D-701	30" RCP, CLASS III	LF	124
30	D-701	36" RCP, CLASS III	LF	400
31	D-701	TRENCH DRAIN	LF	275
32	D-751	DROP INLET, STD DI-7 W/ 48" RISER	EA	4
33	D-751	MANHOLE, STD MH-1 W/ 60" RISER	EA	2
34	T-901	SEEDING	LS	1
35	T-908	MULCHING	LS	1
36	L-110	6" PVC CONDUIT IN TRENCH	LF	245
37	L-110	6" 2 WAY CONCRETE ENCASED DUCTBANK	LF	170
38	L-115	JUNCTION BOX, VDOT JB-4C	EA	13
39	R-309	AGGREGATE BASE COURSE	TN	3,525
40	R-315	BITUMINOUS BASE COURSE, TYPE BM-25.0	TN	1,700
41	R-315	BITUMINOUS SURFACE COURSE, TYPE SM-12.5A	TN	1,275
42	R-606	SOIL RETENTION COVERING	SY	150